

NC Sheriff Association 2021/2022 Heavy Equipment Bid 22-06-0426

Trailer Mounted Tag- Along Grout System Base Unit

Manufacturer		Model Description	
CUES		TRL Trailer mounted Grout System tag Along to TV Unit	
	7X14 TANDEM AXLE TRAILER, 7000GVWR		
	1	7X14 TANDEM AXLE TRAILER, 7000GVWR 1 Tandem Axle Trailer	
	1	LOGIBALL READY SYSTEM TO INCLUDE:1Tow Cable Assembly1Cable Assembly 12 Pin to 5 & 4 Pin Female1Manifold Assembly, Test1Panel Assembly, Motor Pump, Logiball1Cable Installation Kit (Cable End Repair & Terminal Strip)1Reel Mount Vacuum Stand1Cable Assembly, 12 to 5/4/3/ Female1Logiball Power Supply Assembly1Logiball Power Supply Assembly1Cable Panel/Control Box/Vacuum Pump1Cable Panel/Control Box/Logiball1Logiball Exhaust Manifold Assembly1Logiball Air Regulator, Panel Mount10-150 psi Air Regulator, Panel Mount1Vacuum Gauge, Panel Mount1Logiball Posatryn Adapter Assembly	
	2	LOGIBALL SKID RUNNERS	
	1	LOGIBALL PORT TESTER TOOL	
	1 IN(ELECTRIC CABLE REEL MOUNTED ON TOP OF HOSE REEL ASSEMBLY TO CLUDE: 1 500' Gold Multi Conductor Kevlar Fiber Armored Cable, .450" Diameter 1 Terminated 1 Local Controller	
	1	UMBILICAL ELECTRIC CABLE REEL FOR MOUNTING IN EXISTING TV INSPECTION UNIT TO INCLUDE: 1 600' of 8 Conductor Umbilical Cable with Terminations Allowing Operator in TV Unit to: 1 Operate Cutter 1 Operate Cable Reel 1 Operate Air Hose Reel 1 Local Controller 1	
	1	TEST AND SEAL CONTROL PANEL RACK MOUNT TO INCLUDE:1Quick Inflate High Speed Packer Inflation System1Quick Deflate System1Remote Pressure Sensing System	

- 1
- Remote Pressure Sensing System 1
- Pipe Joint Air Test System 1



NC Sheriff Association 2021/2022 Heavy Equipment Bid 22-06-0426

- 1 Pipe Joint Water / Liquid Test System with Leak Rate Loss Flow Meter
- 1 Sealing System Control Panel with:
 - 1 Monitoring Gauges, Pump Controls, and Stroke Counter

1 PENTA HOSE REEL ASSEMBLY W/FITTINGS

- 1 Stainless Steel Dual Passage Rotary Joints
- 1 Electric Reel Drive Motor Control, Reel Mount
- 1 Transmission Control Linkage, Reel Mount
- 1 Hose Terminal Quick Connectors, SS Locking
- 1 Chemical Hose SS Check Valve Assemblies
- 1 Packer Joint Testing / Sealing Adapter with Transducer
- 1 500' Penta Hose

1 SKID ASSY, 6", P&T, CVC, RVC

1 6" Low Profile Camera Skid Assembly

1 8"-30" SKID ASSEMBLY TO INCLUDE:

- 1 8" to 30" Pipe Diameter Skid Spacer Plate
- 2 Bottom Stainless Steel Runners
- 3 Top Stainless Steel Runners

1 CHEMICAL HANDLING PACKAGE, TO INCLUDE:

- 2 Chemical Mixing Paddle
- 1 Chemical Scoop
- 1 Chemical Measuring Cup [Plastic]

1 ELECTRIC WINCH W/1000' 3/16 " SST CABLE TO INCLUDE:

- 1 Hinged, Fold down Frame with Pin Locks
- 1 1 / 2 hp High Torque Power Driver
- 1 3 / 16" Stainless Steel Winch Tow Cable 1000'
- 1 Winch Power Cord Extension Assembly 20'
- 1 Power Winch Drum Emergency Hand Crank
- 1 CONTROLLER FOR ELECTRIC WINCH 110V
- 2 REEL W/500' 14/4 POWER CABLE FOR ELECTRIC WINCH 1 Power Cord Reel Assembly w/500' 14/4 Power Cord
- 1 MANHOLE TOPROLLER ASSEMBLY
- 2 MANHOLE ADAPTER CLAW HOOK
- 6 RETRIEVAL/DOWNHOLE POLE ASSEMBLY
- 3 STEEL RETRIEVAL POLE
- 2 INVERT ROLLER ASSEMBLY
- 1 RETRIEVAL HOOK



1

1

1

TV/SEAL TOOL KIT TO INCLUDE: 1

- Quad Ring for 3/8" Quick Disconnect Quad Ring for 1/2" Quick Disconnect
- 1
- 1 Blow down Swivel Adapter Assembly
- 1 Wash down Swivel Adapter Assembly
- 1 **Electrical Tape**
- 5FT Extension Cable 5/5 1 1
 - Milliamp meter Tool
 - 9-Piece Allen Wrench Kit
- Industrial Pliers 1
- **Needle Nose Pliers** 1
- Six-in-One Screwdriver 1
- 6" Adjustable Wrench 1
 - 1 OZ Anti Seize Grease
- Grout Pump Adjustment Tool 1
- Solder Iron Kit 1
- TV/Seal Training Video 1
- Parts Catalog 1
- 3 M/C TV Only Operation Manual
- 3 **Test/Seal Operations Manual**
- TV Only Training DVD 1
- 5/32 Hex T-Handle Wrench 1
- 2 Solenoid Valve Seal
- 2 Check Valve Repair Kit
- 1 Packer Stem Cleaning Tool

DAYS TRAINING, ON-SITE 2