

**REMOUNT PRICING**

**Version 22.0**

**EXCELLANCE, Inc**

453 Lanier Road, Madison, Alabama 35758

1-800-882-9799

**NCSA FIRE/EMS/LAW ENFORCEMENT  
SPECIALTY VEHICLES PROCUREMENT  
BID 23-03-0524**

**REMOUNT BUILD SHEET - TYPE I-EHD CHEVROLET 4500 4X2 DIESEL**

**CHASSIS**

120  
123 ( 1 ) Excellence Supplied Chassis  
124

ENTER MODEL YEAR FOR NEW CHASSIS:	2023
ENTER MODEL OF NEW CHASSIS:	SILVERADO 4500 4X2
ENTER MAKE OF NEW CHASSIS:	CHEVROLET
ENTER CAB TO AXLE MEASUREMENT OF NEW CHASSIS:	108"
ENTER WHEELBASE MEASUREMENT OF NEW CHASSIS:	193"

**THE REMOUNT WILL HAVE THE FOLLOWING WORK INCLUDED IN THE STANDARD BASE CONVERSION:**

**CHASSIS INSPECTION**

Inspected for damage and defects upon delivery

Test Drive

The chassis shall be inspected against (A) Excellence's Chassis order, and (B) the specifications supplied by the customer/ dealer.

All loose equipment received with the chassis shall be inventoried and stored.

All chassis functions shall be tested for proper operation (accelerator, brakes, headlights, wipers, horn, radio, air conditioner, gauges, dome lights, turn signals, parking lights, etc.).

**CHASSIS WORK TO BE PERFORMED**

Heat Shields shall be installed above the exhaust system.

Chassis shall have undercoating applied.

Exhaust modifications shall be performed as necessary.

Air valve extensions shall be installed on the rear inner tires.

New mounting hardware shall be installed including: Grade 8 bolts, washers, nylon lock-nuts, spacers, outriggers (Type I units only)

New mounting bracket for the rear bumper shall be installed to the chassis frame.

Chassis high idle system shall be connected and operational.

Chassis electrical charging/ battery system shall be connected to the module electrical system.

New Chassis emergency light wiring shall be installed (Grille, Intersection lights, etc.)

## REMOUNT PRICING

### Version 22.0

154 All power cables connecting the chassis electrical system to the modular electrical system shall be replaced.  
155 The chassis fuel fill shall be installed in accordance with current QVM standards.

156 Modular Air conditioning system shall have a vacuum performed and shall be recharged with 134A Freon with  
157 ultra-violet leak identification air conditioning oil dye installed into the system.

The module to chassis heater valves and pump shall be replaced.

158 Chassis to module attachment shall be finished off via Excellance fabricated close out panels and a rubber  
159 seal on a Type III units. A cab to module rubber accordion style boot shall be installed on EHD and Type I  
160 units.

New Front module mounted stone guards.

New back-up alarm

Reattach all existing Radio wiring disconnected from the chassis by Excellance during the remount process.

**THIS IS LIMITED TO TWO (2) RADIO SYSTEMS - ADDITIONAL PRICING WILL BE ADDED FOR VEHICLES WITH  
161 MORE THAN TWO RADIO SYSTEMS.**

162 "No Smoking" Fasten Your Seatbelt" sticker shall be installed in the chassis cab.

#### ADDITIONAL ITEMS TO BE PROVIDED

163 A professional Front End Alignment shall be performed on the chassis upon completion of the remount process.

164 The Fuel tank shall be full of fuel upon completion of the remount process.

165 All chassis engine fluid levels shall be inspected and adjusted as necessary.

166 Chassis tire pressure shall be inspected and adjusted as needed.

167 All hinges, latches, locks, door hold open devices etc. shall be lubricated.

168 Headlights shall be adjusted to the proper level.

169 The interior and exterior of the ambulance body and chassis cab shall be professionally washed and detailed.

#### DOCUMENTS AND CERTIFICATIONS TO BE PROVIDED

170 Excellance shall provide electrical diagrams for all circuits added during the remount process.

171 Vehicle shall have a weight certificate documented and installed on the unit.

172 Air Conditioning shall have a certificate documenting Freon capacity.

173 Oxygen leak test and verification sticker shall be installed on the unit.

174 Upon full payment a "Bill of Sale", "Odometer Statement" and receipt shall be provided.

175 ***UNLESS OTHERWISE SPECIFIED IN THIS ORDER, ITEMS THAT ARE REMOVED DURING THE REMOUNT PROCESS SHALL BE REINSTALLED  
176 IN THE SAME MANNER WITH WHICH THEY WERE ORIGINALLY INSTALLED ONTO THE NEW CHASSIS AND MODULE BODY. VEHICLES WITH EXCESSIVE  
177 EQUIPMENT MAY INCUR ADDED CHARGES FOR EQUIPMENT TO BE TRANSFERRED.***

178 ***ALSO INCLUDED IN THE BASE PRICE FOR "REMOUNTING" AN AMBULANCE:***

179 **EXCELLANCE WILL PERFORM THE FOLLOWING TASKS UPON THE UNIT ARRIVING AT THE FACTORY:**

180 **Physical Inspection of the Exterior body to include:**

181 **Structural Damage**

182 **Condition of paint**

183 **Condition of striping and lettering**

184 **light housings**

185 **Door hardware (handles, hinges & door frames)**

**REMOUNT PRICING**  
**Version 22.0**

192 **Window Frames**  
193 **Walk- Through or Pass-Through rubber boots (if applicable)**  
194 **Bumper step (hinges, screws, rivets, rubber dock bumpers)**  
195 **Compartment doors (handles, hinges, skins, drains, venting, etc.)**

196  
197 **Physical inspection of the Interior Patient Compartment to include:**  
198 **Floor Covering**  
199 **Formica**  
200 **IV hangers**  
201 **Cot Hardware**  
202 **O2 outlets**  
203 **Trim (upholstery, aluminum and Trim Lock")**  
204 **Cabinetry (hinges, slides, unistrut, shelves, Plexiglas)**  
205 **Upholstery (seats, head-knockers, arm-rests, etc.)**  
206 **Countertops**  
207 **Attendant Seat and seat base**  
208 **Drawers (slides, latches, etc.)**  
209 **Lighting (lenses, switches, outlets, etc.)**  
210 **Electrical Cabinet (blown fuses, loose wiring, wire chafing, missing components, etc.)**  
211

212 ***ALL LOOSE EQUIPMENT ARRIVING WITH THE VEHICLE SHALL BE INVENTORIED, DOCUMENTED AND STORED UPON THE UNIT ARRIVAL TO THE***  
213 ***FACTORY.***

214 ***EXCELLANCE SHALL NOT BE RESPONSIBLE FOR UNDOCUMENTED LOOSE EQUIPMENT LEFT IN THE VEHICLE.***

215 ***PHOTOGRAPHS TO DOCUMENT THE CONDITION OF THE UNIT SHALL BE TAKEN UPON THE UNIT ARRIVAL TO THE FACTORY.***

216 ***ANY ADDITIONAL COSTS DUE TO WORK DEEMED NECESSARY BY EXCELLANCE TO THE MODULAR BODY OR CUSTOMER/ DEALER SUPPLIED***  
217 ***CHASSIS SHALL BE ASSESSED AS EARLY AS POSSIBLE DURING THE REMOUNT PROCESS. THE CUSTOMER/ DEALER SHALL BE NOTIFIED OF***  
218 ***THE NECESSARY WORK AND ASSOCIATED COSTS FOR THEIR WRITTEN APPROVAL.***

219  
220  
221  
222  
223  
224  
225  
226  
227  
228  
229  
230  
231  
232  
233  
234  
235 **BASE REMOUNT**  
236 **IF CHOOSING THE SAME BRAND AND MODEL CHASSIS**

240 ( 1 ) Excellence EHD

245  
246  
247  
248  
249  
250  
251  
252  
253  
254  
255  
256  
257  
258  
259  
260  
261  
262  
263  
264  
265  
266  
267  
268  
269  
270  
271  
272  
273 **EXCELLANCE CAB & CHASSIS**

280 **EXCELLANCE LITERATURE**  
281 ( 1 ) ***Wiring diagram of all conversion circuits and Excellence changes & additions***

284  
285  
286  
287  
288  
289  
290  
291  
292  
293  
294  
295  
296  
297  
298  
299  
300  
301  
302  
303  
304  
305  
306  
307  
308  
309  
310  
311  
312  
313  
314  
315  
316  
317  
318  
319  
320  
321  
322  
323  
324  
325  
326  
327  
328  
329  
330  
331  
332  
333  
334  
335 **SUSPENSION / DRIVE TRAIN**  
336 ***NOTE: WEIGHT ADVISORY: Suspension systems will affect GVW and payload availability.***  
349 ( 1 ) Rear Liquid Spring Suspension for Chevrolet 4500

**REMOUNT PRICING**  
**Version 22.0**

352

**REAR SUSPENSION CONTROLS** *Note: All Rear suspension systems will be equipped with a suspension  
down indicator light located on the cab console.*

361

1 Operate the new suspension system utilizing a magnetic switch on the left rear entry door when opened. There shall  
be an override switch on the inside face primary rear entry door. *This line should be selected if a suspension system*

363

( 1 ) *is new to the ambulance body with the new chassis.*

370

**CHASSIS WHEEL COVER**

390

393

( 1 ) DELETION CREDIT- Do not paint the outer rims of the chassis with white Krylon paint.

404

707

**MODULAR BODY:**

708

**L-1 COMPARTMENT**

709

*No additional work to be done to this compartment*

773

**L-3 Compartment**

774

*No additional work to be done to this compartment*

838

**L-4 Compartment**

839

*No additional work to be done to this compartment*

903

**R-1 Compartment**

904

*No additional work to be done to this compartment*

968

**R-2 Compartment**

969

*No additional work to be done to this compartment*

1033

**R-4 Compartment**

1034

*No additional work to be done to this compartment*