

REMOUNT PRICING

Version 22.0

EXCELLANCE, Inc

453 Lanier Road, Madison, Alabama 35758

1-800-882-9799

**NCSA FIRE/EMS/LAW ENFORCEMENT
SPECIALTY VEHICLES PROCUREMENT
BID 23-03-0524**

REMOUNT BUILD SHEET - TYPE III L FORD E450 GAS

CHASSIS

120
123 (1) Excellance Supplied Chassis
124

ENTER MODEL YEAR FOR NEW CHASSIS:	2023
ENTER MODEL OF NEW CHASSIS:	E450 GAS
ENTER MAKE OF NEW CHASSIS:	FORD
ENTER CAB TO AXLE MEASUREMENT OF NEW CHASSIS:	100"
ENTER WHEELBASE MEASUREMENT OF NEW CHASSIS:	158"

THE REMOUNT WILL HAVE THE FOLLOWING WORK INCLUDED IN THE STANDARD BASE CONVERSION:

CHASSIS INSPECTION

Inspected for damage and defects upon delivery

Test Drive

The chassis shall be inspected against (A) Excellance's Chassis order, and (B) the specifications supplied by the customer/ dealer.

All loose equipment received with the chassis shall be inventoried and stored.

All chassis functions shall be tested for proper operation (accelerator, brakes, headlights, wipers, horn, radio, air conditioner, gauges, dome lights, turn signals, parking lights, etc.).

CHASSIS WORK TO BE PERFORMED

Heat Shields shall be installed above the exhaust system.

Chassis shall have undercoating applied.

Exhaust modifications shall be performed as necessary.

Air valve extensions shall be installed on the rear inner tires.

New mounting hardware shall be installed including: Grade 8 bolts, washers, nylon lock-nuts, spacers, outriggers (Type I units only)

New mounting bracket for the rear bumper shall be installed to the chassis frame.

Chassis high idle system shall be connected and operational.

Chassis electrical charging/ battery system shall be connected to the module electrical system.

New Chassis emergency light wiring shall be installed (Grille, Intersection lights, etc.)

All power cables connecting the chassis electrical system to the modular electrical system shall be replaced.

REMOUNT PRICING

Version 22.0

155 The chassis fuel fill shall be installed in accordance with current QVM standards.

156 Modular Air conditioning system shall have a vacuum performed and shall be recharged with 134A Freon with
157 ultra-violet leak identification air conditioning oil dye installed into the system.

158 The module to chassis heater valves and pump shall be replaced.

159 Chassis to module attachment shall be finished off via Excellance fabricated close out panels and a rubber
160 seal on a Type III units. A cab to module rubber accordion style boot shall be installed on EHD and Type I
161 units.

162 New Front module mounted stone guards.

163 New back-up alarm

164 Reattach all existing Radio wiring disconnected from the chassis by Excellance during the remount process.

165 **THIS IS LIMITED TO TWO (2) RADIO SYSTEMS - ADDITIONAL PRICING WILL BE ADDED FOR VEHICLES WITH
166 MORE THAN TWO RADIO SYSTEMS.**

167 "No Smoking" Fasten Your Seatbelt" sticker shall be installed in the chassis cab.

ADDITIONAL ITEMS TO BE PROVIDED

168 A professional Front End Alignment shall be performed on the chassis upon completion of the remount process.

169 The Fuel tank shall be full of fuel upon completion of the remount process.

170 All chassis engine fluid levels shall be inspected and adjusted as necessary.

171 Chassis tire pressure shall be inspected and adjusted as needed.

172 All hinges, latches, locks, door hold open devices etc. shall be lubricated.

173 Headlights shall be adjusted to the proper level.

174 The interior and exterior of the ambulance body and chassis cab shall be professionally washed and detailed.

DOCUMENTS AND CERTIFICATIONS TO BE PROVIDED

175 Excellance shall provide electrical diagrams for all circuits added during the remount process.

176 Vehicle shall have a weight certificate documented and installed on the unit.

177 Air Conditioning shall have a certificate documenting Freon capacity.

178 Oxygen leak test and verification sticker shall be installed on the unit.

179 Upon full payment a "Bill of Sale", "Odometer Statement" and receipt shall be provided.

180 ***UNLESS OTHERWISE SPECIFIED IN THIS ORDER, ITEMS THAT ARE REMOVED DURING THE REMOUNT PROCESS SHALL BE REINSTALLED
181 IN THE SAME MANNER WITH WHICH THEY WERE ORIGINALLY INSTALLED ONTO THE NEW CHASSIS AND MODULE BODY. VEHICLES WITH EXCESSIVE
182 EQUIPMENT MAY INCUR ADDED CHARGES FOR EQUIPMENT TO BE TRANSFERRED.***

183 ***ALSO INCLUDED IN THE BASE PRICE FOR "REMOUNTING" AN AMBULANCE:***

184 **EXCELLANCE WILL PERFORM THE FOLLOWING TASKS UPON THE UNIT ARRIVING AT THE FACTORY:**

185 **Physical Inspection of the Exterior body to include:**

186 **Structural Damage**

187 **Condition of paint**

188 **Condition of striping and lettering**

189 **light housings**

190 **Door hardware (handles, hinges & door frames)**

191 **Window Frames**

REMOUNT PRICING

Version 22.0

193 Walk- Through or Pass-Through rubber boots (if applicable)
194 Bumper step (hinges, screws, rivets, rubber dock bumpers)
195 Compartment doors (handles, hinges, skins, drains, venting, etc.)

196
197 **Physical inspection of the Interior Patient Compartment to include:**

198 Floor Covering
199 Formica
200 IV hangers
201 Cot Hardware
202 02 outlets
203 Trim (upholstery, aluminum and Trim Lock")
204 Cabinetry (hinges, slides, unistrut, shelves, Plexiglas)
205 Upholstery (seats, head-knockers, arm-rests, etc.)
206 Countertops
207 Attendant Seat and seat base
208 Drawers (slides, latches, etc.)
209 Lighting (lenses, switches, outlets, etc.)
210 Electrical Cabinet (blown fuses, loose wiring, wire chafing, missing components, etc.)
211

212 ***ALL LOOSE EQUIPMENT ARRIVING WITH THE VEHICLE SHALL BE INVENTORIED, DOCUMENTED AND STORED UPON THE UNIT ARRIVAL TO THE***
213 ***FACTORY.***

214 ***EXCELLANCE SHALL NOT BE RESPONSIBLE FOR UNDOCUMENTED LOOSE EQUIPMENT LEFT IN THE VEHICLE.***

215 ***PHOTOGRAPHS TO DOCUMENT THE CONDITION OF THE UNIT SHALL BE TAKEN UPON THE UNIT ARRIVAL TO THE FACTORY.***

216 ***ANY ADDITIONAL COSTS DUE TO WORK DEEMED NECESSARY BY EXCELLANCE TO THE MODULAR BODY OR CUSTOMER/ DEALER SUPPLIED***
217 ***CHASSIS SHALL BE ASSESSED AS EARLY AS POSSIBLE DURING THE REMOUNT PROCESS. THE CUSTOMER/ DEALER SHALL BE NOTIFIED OF***
218 ***THE NECESSARY WORK AND ASSOCIATED COSTS FOR THEIR WRITTEN APPROVAL.***

219
235 **BASE REMOUNT**
236 **IF CHOOSING THE SAME BRAND AND MODEL CHASSIS**

239 (1) Excellence Type III Long Super Duty
245

272
273 **EXCELLANCE CAB & CHASSIS**

280 **EXCELLANCE LITERATURE**

281 (1) ***Wiring diagram of all conversion circuits and Excellence changes & additions***
284

335 **SUSPENSION / DRIVE TRAIN**

390 **CHASSIS WHEEL COVER**

393 (1) ***DELETION CREDIT- Do not paint the outer rims of the chassis with white Krylon paint.***
404

REMOUNT PRICING
Version 22.0

MODULAR BODY:

707 **L-1 COMPARTMENT**
708 *No additional work to be done to this compartment*
709
773 **L-3 Compartment**
774 *No additional work to be done to this compartment*
838 **L-4 Compartment**
839 *No additional work to be done to this compartment*
903 **R-1 Compartment**
904 *No additional work to be done to this compartment*
968 **R-2 Compartment**
969 *No additional work to be done to this compartment*
1033 **R-4 Compartment**
1034 *No additional work to be done to this compartment*