

REMOUNT PRICING

Version 22.0

EXCELLANCE, Inc

453 Lanier Road, Madison, Alabama 35758
1-800-882-9799

NCSA FIRE/EMS/LAW ENFORCEMENT
SPECIALTY VEHICLES PROCUREMENT
BID 23-03-0524

REMOUNT BUILD SHEET - TYPE I-L DODGE RAM 4500 4X2 DIESEL

CHASSIS

120
123 (1) Excellance Supplied Chassis
124

ENTER MODEL YEAR FOR NEW CHASSIS:	2023
ENTER MODEL OF NEW CHASSIS:	RAM 4500 4X2 DIESEL
ENTER MAKE OF NEW CHASSIS:	DODGE
ENTER CAB TO AXLE MEASUREMENT OF NEW CHASSIS:	108"
ENTER WHEELBASE MEASUREMENT OF NEW CHASSIS:	193"

THE REMOUNT WILL HAVE THE FOLLOWING WORK INCLUDED IN THE STANDARD BASE CONVERSION:

CHASSIS INSPECTION

Inspected for damage and defects upon delivery

Test Drive

The chassis shall be inspected against (A) Excellance's Chassis order, and (B) the specifications supplied by the customer/ dealer.

All loose equipment received with the chassis shall be inventoried and stored.

All chassis functions shall be tested for proper operation (accelerator, brakes, headlights, wipers, horn, radio, air conditioner, gauges, dome lights, turn signals, parking lights, etc.).

CHASSIS WORK TO BE PERFORMED

Heat Shields shall be installed above the exhaust system.

Chassis shall have undercoating applied.

Exhaust modifications shall be performed as necessary.

Air valve extensions shall be installed on the rear inner tires.

New mounting hardware shall be installed including: Grade 8 bolts, washers, nylon lock-nuts, spacers, outriggers (Type I units only)

New mounting bracket for the rear bumper shall be installed to the chassis frame.

Chassis high idle system shall be connected and operational.

Chassis electrical charging/ battery system shall be connected to the module electrical system.

New Chassis emergency light wiring shall be installed (Grille, Intersection lights, etc.)

All power cables connecting the chassis electrical system to the modular electrical system shall be replaced.

The chassis fuel fill shall be installed in accordance with current QVM standards.

REMOUNT PRICING

Version 22.0

156 Modular Air conditioning system shall have a vacuum performed and shall be recharged with 134A Freon with
157 ultra-violet leak identification air conditioning oil dye installed into the system.

The module to chassis heater valves and pump shall be replaced.

158 Chassis to module attachment shall be finished off via Excellance fabricated close out panels and a rubber
159 seal on a Type III units. A cab to module rubber accordion style boot shall be installed on EHD and Type I
160 units.

New Front module mounted stone guards.

New back-up alarm

Reattach all existing Radio wiring disconnected from the chassis by Excellance during the remount process.

**THIS IS LIMITED TO TWO (2) RADIO SYSTEMS - ADDITIONAL PRICING WILL BE ADDED FOR VEHICLES WITH
161 MORE THAN TWO RADIO SYSTEMS.**

162 "No Smoking" Fasten Your Seatbelt" sticker shall be installed in the chassis cab.

ADDITIONAL ITEMS TO BE PROVIDED

163 A professional Front End Alignment shall be performed on the chassis upon completion of the remount process.

164 The Fuel tank shall be full of fuel upon completion of the remount process.

165 All chassis engine fluid levels shall be inspected and adjusted as necessary.

166 Chassis tire pressure shall be inspected and adjusted as needed.

167 All hinges, latches, locks, door hold open devices etc. shall be lubricated.

168 Headlights shall be adjusted to the proper level.

169 The interior and exterior of the ambulance body and chassis cab shall be professionally washed and detailed.
170
171
172
173

DOCUMENTS AND CERTIFICATIONS TO BE PROVIDED

174 Excellance shall provide electrical diagrams for all circuits added during the remount process.

175 Vehicle shall have a weight certificate documented and installed on the unit.

176 Air Conditioning shall have a certificate documenting Freon capacity.

177 Oxygen leak test and verification sticker shall be installed on the unit.

178 Upon full payment a "Bill of Sale", "Odometer Statement" and receipt shall be provided.
179
180
181

***UNLESS OTHERWISE SPECIFIED IN THIS ORDER, ITEMS THAT ARE REMOVED DURING THE REMOUNT PROCESS SHALL BE REINSTALLED
182 IN THE SAME MANNER WITH WHICH THEY WERE ORIGINALLY INSTALLED ONTO THE NEW CHASSIS AND MODULE BODY. VEHICLES WITH EXCESSIVE
183 EQUIPMENT MAY INCUR ADDED CHARGES FOR EQUIPMENT TO BE TRANSFERRED.***

ALSO INCLUDED IN THE BASE PRICE FOR "REMOUNTING" AN AMBULANCE:

EXCELLANCE WILL PERFORM THE FOLLOWING TASKS UPON THE UNIT ARRIVING AT THE FACTORY:

Physical Inspection of the Exterior body to include:

187 Structural Damage

188 Condition of paint

189 Condition of striping and lettering

190 light housings

191 Door hardware (handles, hinges & door frames)

192 Window Frames

193 Walk- Through or Pass-Through rubber boots (if applicable)

REMOUNT PRICING
Version 22.0

194 Bumper step (hinges, screws, rivets, rubber dock bumpers)
195 Compartment doors (handles, hinges, skins, drains, venting, etc.)

196 **Physical inspection of the Interior Patient Compartment to include:**

197 **Floor Covering**
198 **Formica**
199 **IV hangers**
200 **Cot Hardware**
201 **02 outlets**
202 **Trim (upholstery, aluminum and Trim Lock")**
203 **Cabinetry (hinges, slides, unistrut, shelves, Plexiglas)**
204 **Upholstery (seats, head-knockers, arm-rests, etc.)**
205 **Countertops**
206 **Attendant Seat and seat base**
207 **Drawers (slides, latches, etc.)**
208 **Lighting (lenses, switches, outlets, etc.)**
209 **Electrical Cabinet (blown fuses, loose wiring, wire chafing, missing components, etc.)**
210
211

212 ***ALL LOOSE EQUIPMENT ARRIVING WITH THE VEHICLE SHALL BE INVENTORIED, DOCUMENTED AND STORED UPON THE UNIT ARRIVAL TO THE***
213 ***FACTORY.***

214 ***EXCELLANCE SHALL NOT BE RESPONSIBLE FOR UNDOCUMENTED LOOSE EQUIPMENT LEFT IN THE VEHICLE.***

215 ***PHOTOGRAPHS TO DOCUMENT THE CONDITION OF THE UNIT SHALL BE TAKEN UPON THE UNIT ARRIVAL TO THE FACTORY.***

216 ***ANY ADDITIONAL COSTS DUE TO WORK DEEMED NECESSARY BY EXCELLANCE TO THE MODULAR BODY OR CUSTOMER/ DEALER SUPPLIED***
217 ***CHASSIS SHALL BE ASSESSED AS EARLY AS POSSIBLE DURING THE REMOUNT PROCESS. THE CUSTOMER/ DEALER SHALL BE NOTIFIED OF***
218 ***THE NECESSARY WORK AND ASSOCIATED COSTS FOR THEIR WRITTEN APPROVAL.***

219
235 **BASE REMOUNT**

236 **IF CHOOSING THE SAME BRAND AND MODEL CHASSIS**

237 (1) Excellence Type I
245

272
273 **EXCELLANCE CAB & CHASSIS**

280 **EXCELLANCE LITERATURE**

281 (1) ***Wiring diagram of all conversion circuits and Excellence changes & additions***
284

335 **SUSPENSION / DRIVE TRAIN**

336 ***NOTE: WEIGHT ADVISORY: Suspension systems will affect GVW and payload availability.***

349 (1) Rear Liquid Spring Suspension for Dodge RAM 4500
352

REMOUNT PRICING

Version 22.0

REAR SUSPENSION CONTROLS *Note: All Rear suspension systems will be equipped with a suspension
down indicator light located on the cab console.*

361 1 Operate the new suspension system utilizing a magnetic switch on the left rear entry door when opened. There shall
be an override switch on the inside face primary rear entry door. *This line should be selected if a suspension system*
363 (1) *is new to the ambulance body with the new chassis.*

CHASSIS WHEEL COVER

393 (1) DELETION CREDIT- Do not paint the outer rims of the chassis with white Krylon paint.

MODULAR BODY:

L-1 COMPARTMENT

No additional work to be done to this compartment

L-3 Compartment

No additional work to be done to this compartment

L-4 Compartment

No additional work to be done to this compartment

R-1 Compartment

No additional work to be done to this compartment

R-2 Compartment

No additional work to be done to this compartment

R-4 Compartment

No additional work to be done to this compartment