

**REMOUNT PRICING**

**Version 22.0**

**EXCELLANCE, Inc**

453 Lanier Road, Madison, Alabama 35758

1-800-882-9799

NCSA FIRE/EMS/LAW ENFORCEMENT  
SPECIALTY VEHICLES PROCUREMENT  
BID 23-03-0524

**REMOUNT BUILD SHEET - FORD F-450 4X2 DIESEL**

**CHASSIS**

120  
123 ( 1 ) Excellance Supplied Chassis  
124

ENTER MODEL YEAR FOR NEW CHASSIS:	2023
ENTER MODEL OF NEW CHASSIS:	F450 4X2 DIESEL
ENTER MAKE OF NEW CHASSIS:	FORD
ENTER CAB TO AXLE MEASUREMENT OF NEW CHASSIS:	108"
ENTER WHEELBASE MEASUREMENT OF NEW CHASSIS:	193"

**THE REMOUNT WILL HAVE THE FOLLOWING WORK INCLUDED IN THE STANDARD BASE CONVERSION:**

**CHASSIS INSPECTION**

Inspected for damage and defects upon delivery

Test Drive

The chassis shall be inspected against (A) Excellance's Chassis order, and (B) the specifications supplied by the customer/ dealer.

All loose equipment received with the chassis shall be inventoried and stored.

All chassis functions shall be tested for proper operation (accelerator, brakes, headlights, wipers, horn, radio, air conditioner, gauges, dome lights, turn signals, parking lights, etc.).

**CHASSIS WORK TO BE PERFORMED**

Heat Shields shall be installed above the exhaust system.

Chassis shall have undercoating applied.

Exhaust modifications shall be performed as necessary.

Air valve extensions shall be installed on the rear inner tires.

New mounting hardware shall be installed including: Grade 8 bolts, washers, nylon lock-nuts, spacers, outriggers (Type I units only)

New mounting bracket for the rear bumper shall be installed to the chassis frame.

Chassis high idle system shall be connected and operational.

Chassis electrical charging/ battery system shall be connected to the module electrical system.

New Chassis emergency light wiring shall be installed (Grille, Intersection lights, etc.)

All power cables connecting the chassis electrical system to the modular electrical system shall be replaced.

The chassis fuel fill shall be installed in accordance with current QVM standards.

Modular Air conditioning system shall have a vacuum performed and shall be recharged with 134A Freon with ultra-violet leak identification air conditioning oil dye installed into the system.

## REMOUNT PRICING

### Version 22.0

157  
158  
159  
160  
161  
162  
163  
164  
165  
166  
167  
168  
169  
170  
171  
173  
174  
175  
176  
177  
178  
179  
180  
181  
182  
183  
184  
185  
186  
187  
188  
189  
190  
191  
192  
193  
194  
195

The module to chassis heater valves and pump shall be replaced.

Chassis to module attachment shall be finished off via Excellance fabricated close out panels and a rubber seal on a Type III units. A cab to module rubber accordion style boot shall be installed on EHD and Type I units.

New Front module mounted stone guards.

New back-up alarm

Reattach all existing Radio wiring disconnected from the chassis by Excellance during the remount process.

**THIS IS LIMITED TO TWO (2) RADIO SYSTEMS - ADDITIONAL PRICING WILL BE ADDED FOR VEHICLES WITH MORE THAN TWO RADIO SYSTEMS.**

"No Smoking" Fasten Your Seatbelt" sticker shall be installed in the chassis cab.

#### ADDITIONAL ITEMS TO BE PROVIDED

A professional Front End Alignment shall be performed on the chassis upon completion of the remount process.

The Fuel tank shall be full of fuel upon completion of the remount process.

All chassis engine fluid levels shall be inspected and adjusted as necessary.

Chassis tire pressure shall be inspected and adjusted as needed.

All hinges, latches, locks, door hold open devices etc. shall be lubricated.

Headlights shall be adjusted to the proper level.

The interior and exterior of the ambulance body and chassis cab shall be professionally washed and detailed.

#### DOCUMENTS AND CERTIFICATIONS TO BE PROVIDED

Excellance shall provide electrical diagrams for all circuits added during the remount process.

Vehicle shall have a weight certificate documented and installed on the unit.

Air Conditioning shall have a certificate documenting Freon capacity.

Oxygen leak test and verification sticker shall be installed on the unit.

Upon full payment a "Bill of Sale", "Odometer Statement" and receipt shall be provided.

**UNLESS OTHERWISE SPECIFIED IN THIS ORDER, ITEMS THAT ARE REMOVED DURING THE REMOUNT PROCESS SHALL BE REINSTALLED IN THE SAME MANNER WITH WHICH THEY WERE ORIGINALLY INSTALLED ONTO THE NEW CHASSIS AND MODULE BODY. VEHICLES WITH EXCESSIVE EQUIPMENT MAY INCUR ADDED CHARGES FOR EQUIPMENT TO BE TRANSFERRED.**

**ALSO INCLUDED IN THE BASE PRICE FOR "REMOUNTING" AN AMBULANCE:**

**EXCELLANCE WILL PERFORM THE FOLLOWING TASKS UPON THE UNIT ARRIVING AT THE FACTORY:**

**Physical Inspection of the Exterior body to include:**

Structural Damage

Condition of paint

Condition of striping and lettering

light housings

Door hardware (handles, hinges & door frames)

Window Frames

Walk- Through or Pass-Through rubber boots (if applicable)

Bumper step (hinges, screws, rivets, rubber dock bumpers)

Compartment doors (handles, hinges, skins, drains, venting, etc.)

**REMOUNT PRICING**  
**Version 22.0**

196  
197  
198  
199  
200  
201  
202  
203  
204  
205  
206  
207  
208  
209  
210  
211

- Physical inspection of the Interior Patient Compartment to include:**
- Floor Covering**
  - Formica**
  - IV hangers**
  - Cot Hardware**
  - O2 outlets**
  - Trim (upholstery, aluminum and Trim Lock")**
  - Cabinetry (hinges, slides, unistrut, shelves, Plexiglas)**
  - Upholstery (seats, head-knockers, arm-rests, etc.)**
  - Countertops**
  - Attendant Seat and seat base**
  - Drawers (slides, latches, etc.)**
  - Lighting (lenses, switches, outlets, etc.)**
  - Electrical Cabinet (blown fuses, loose wiring, wire chafing, missing components, etc.)**

212  
213  
214  
215  
216  
217  
218  
219

**ALL LOOSE EQUIPMENT ARRIVING WITH THE VEHICLE SHALL BE INVENTORIED, DOCUMENTED AND STORED UPON THE UNIT ARRIVAL TO THE FACTORY.**

**EXCELLANCE SHALL NOT BE RESPONSIBLE FOR UNDOCUMENTED LOOSE EQUIPMENT LEFT IN THE VEHICLE.**

**PHOTOGRAPHS TO DOCUMENT THE CONDITION OF THE UNIT SHALL BE TAKEN UPON THE UNIT ARRIVAL TO THE FACTORY.**

**ANY ADDITIONAL COSTS DUE TO WORK DEEMED NECESSARY BY EXCELLANCE TO THE MODULAR BODY OR CUSTOMER/ DEALER SUPPLIED CHASSIS SHALL BE ASSESSED AS EARLY AS POSSIBLE DURING THE REMOUNT PROCESS. THE CUSTOMER/ DEALER SHALL BE NOTIFIED OF THE NECESSARY WORK AND ASSOCIATED COSTS FOR THEIR WRITTEN APPROVAL.**

235  
236

**BASE REMOUNT**  
**IF CHOOSING THE SAME BRAND AND MODEL CHASSIS**

237 ( 1 ) Excellance Type I

245  
273

**EXCELLANCE CAB & CHASSIS OPTIONS**

**EXCELLANCE LITERATURE**

281 ( 1 ) **Wiring diagram of all conversion circuits and Excellance changes & additions**

284  
335

**SUSPENSION / DRIVE TRAIN**

336 **NOTE: WEIGHT ADVISORY: Suspension systems will affect GVW and payload availability.**

346 ( 1 ) Rear Liquid Spring Suspension for F350/F450

352

**REAR SUSPENSION CONTROLS** **Note: All Rear suspension systems will be equipped with a suspension down indicator light located on the cab console.**

361

**REMOUNT PRICING**

**Version 22.0**

363 ( 1 ) Operate the new suspension system utilizing a magnetic switch on the left rear entry door when opened. There shall  
370 be an override switch on the inside face primary rear entry door. *This line should be selected if a suspension system*  
393 ( 1 ) *is new to the ambulance body with the new chassis.*

**CHASSIS WHEEL COVER OPTIONS**

393 ( 1 ) DELETION CREDIT- Do not paint the outer rims of the chassis with white Krylon paint.

**MODULAR BODY:**

**L-1 COMPARTMENT**

No additional work to be done to this compartment

**L-3 Compartment**

No additional work to be done to this compartment

**L-4 Compartment**

No additional work to be done to this compartment

**R-1 Compartment**

No additional work to be done to this compartment

**R-2 Compartment**

No additional work to be done to this compartment

**R-4 Compartment**

No additional work to be done to this compartment