

Specs for the DPR-ATVC bus

- Provide Valor EMT ambulance seat with mounting base, includes backing plates
- Provide and install L-Track along each side of center aisle
- Provide and install O2 tank racks includes vertical bracket fabrication
- Provide and install workstation desk base structure
- Provide and install desk counter
- Provide and install chair tie downs under workstation
- Provide and install OTS 2- drawer base cabinet, right side under workstation counter top
- Provide rolling office style chair, secured when in motion
- Provide and install Whelen 295SLSA6 siren
- Provide and install Whelen SA315P with bracket
- Provide and install Whelen M6 series Super LED Warning lights red
- Provide and install Whelen M6 Chrome flanges
- Provide and install Whelen M9 series Super LED Warning Light Red
- Provided and install M9 chrome flanges
- Provided and install Whelen Ion warning lights RED
- Provide and install Whelen M9LZC Gradient LED Scene Lights
- Provide and install Circuit protection and power distribution for warning
- Provide and Install Shore Power and 30A to 15A Shoreline Adapter
- Modify rear existing body for installation of taller rear door
- (4) 12 V DC Battery System with Isolators and power distribution system
- Installed 30-amp 50 ft shore power cord w/ adapter
- (5) interior 15-amp duplex outlets with USB
- (1) exterior 15-amp duplex GFCI outlet
- (1) Xantrex Freedom X2000 Inverter w/ remote panel
- Install Xantrex TrueCharge 40. Wired: to charge Battery
- Install power distribution and circuit protection for system
- Install custom manual transfer switch for AC source input (3 position +off)
- Install Cummins 7kw gas generator
- Install Control Panel
- Install Generator Compartment
- Install fuel tap system in fuel tank
- Install AGM battery for generator
- Install additional Penquin II Heat Pump 13,500 btu
- Install CO2 detector
- \$4,000 allowance for Graphics