

COMPACTION CONTAINERS - OPTIONS

OPTION	2021
UNDERSTRUCTURE OPTIONS	
Heil	\$1,174
Hook Lift	1,205
Superior	540
National Challenge	270
Brantford	341
Other west coast understructures	550
Dempster Dino	3,558
RAIL, CROSS MEMBER, & UNDERSTRUCTURE FLOOR THICKNESS OPTIONS	
Heavy duty understructure package – 12" cross member spacing, & 1/4" understructure floor	\$1,767
1/4" rails (3/16" standard on OC's / 3/8" standard on XHD's)	725
12" cross member spacing - Standard is 20" (Standard on RJ-40 OC XHD)	567
1/4" understructure floor (Standard on RJ-40 OC XHD)	1,216
3/8" rails (Standard on RJ-40 OC XHD)	1,137
Solid rod door pins and HD latch (Standard on RJ-40 OC XHD)	1,040
6" channel rails in lieu of standard 6" x 2" x 3/16" tubing rails	787
DUMP DOOR OPTIONS	
No Opening - Solid dump door	\$686
Special width or height opening - <u>MUST BE REVIEWED & APPROVED BY ENGINEERING</u>	961
Raised opening with no door seal - <u>MUST BE REVIEWED & APPROVED BY ENGINEERING</u>	961
Ratchet latch & door seal - OC only	1,735
Canvas door cover	209
Hinged door closure option for dump door opening	2,272
Dump door hinged opposite (Standard hinge on RH side)	996
CUSTOM HEIGHT, WIDTH, & LENGTH OPTIONS	
89" overall height (Standard on RJ-16 OC & RJ-20 OC)	\$1,511
Custom overall heights other than standard 104" & 89" - <u>MUST BE REVIEWED & APPROVED BY ENGINEERING</u>	3,778
84" overall width	1,511
Custom overall lengths - <u>MUST BE REVIEWED & APPROVED BY ENGINEERING</u>	2,473
OTHER OPTIONS & MODIFICATIONS	
Front Ground Rollers	\$384
Cushioned ground rollers in lieu of standard steel roller - Only available on standard duty containers	497
Single pin-off system - Container only - <u>MUST ALSO ADD PIN OFF SYSTEM TO COMPACTOR</u>	1,247
Dual pin-off system - Container only - <u>MUST ALSO ADD PIN OFF SYSTEM TO COMPACTOR</u>	2,182
Through-the-wall ratchet kit - <u>MUST ALSO ADD SEPARATE OPTION TO COMPACTOR</u>	384
Extra belly band	1,277

Belly-band - Standard on RJ-40 OC XHD	2,727
Container modifications for DRC-III setup	1,573
Bottom hook up for single side ratchet on compactor - Container only - <u>MUST ALSO ADD OPTION TO COMPACTOR</u>	686
Rear hold-downs - Must request & specify location	NO CHARGE
Stand to elevate OC - Stand up to 60" OAH from ground to top of stand	12,051
<i>PAINT, COATING, & IDENTIFICATION OPTIONS</i>	
Deduct for Prime only	(128)
Non-standard paint color	446
Extra gallon of standard paint	159
Extra gallon of custom paint	199
Rhino Liner - 1/2 Container	2,071
Rhino Liner - Full Container (minus roof)	2,848
2" Reflective Striping - Located on each side & end	263
Weld-on Identification - ID numbers/letters laser cut on 7 ga & welded to unit	105