



SALES QUOTATION

DATE	PAGE
4/20/2022	1

QUANTITY	DESCRIPTION	LIST PRICE EACH	EXT. LIST PRICE
1	QUOTE 161273-4: 12' MK4 BASIC ISG CONFIGURATION 1-1: Mark IV contractor dump body DESCRIPTION: DBM4 12' body length 13" side height, fixed sides None : Body Size / Style Body Length: 12' body length Body Side Style: 13" side height, fixed sides Sloped Steel Side Boards: None Hoist/Hydraulics Hoist: Trunion Mount Tele Hoist M110-4.5-3 (17.1T Class 60) Hydraulics: Direct mount pump & 20 gal. side-mount reservoir Body Hinge Body Hinge Paint: Yes, Rear Hinge Painted @ Factory Materials/Construction Floor Material: Standard 3/16" GR50 steel Tailgate Options Tailgate Latch: Standard tailgate requires pin removal for laydown Tailgate Dump Release: Manual Over-Center release Coal Chute: No Cabshield Options Weld-on Cabshield: 16" x 78" carbon steel Install Cabshield: No Cabshield Window, 12" x 24": 12 GA carbon steel, punched Miscellaneous Options Stake Pockets (shipped loose): No Rubber Mounting Pads: No		