



P.O. Box 3217
Burlington N.C. 27215-3217
(336) 228-1722 • FAX (336) 228-7205
Physical Address: 614 East Hanover Road, Graham, NC 27253

We are pleased to quote the VERSALIFT VANTEL-29-NE non-insulated 28' 10" telescopic aerial platform lift with a 33' 10" working height, including:

Standard platform capacity of 350 lbs.
Heavy duty aluminum inner boom with drop down boom tip.
Drop down boom tip including manual 180° positioner.
Engine start/stop controls at platform and remote lower controls.
Non-continuous 360 degree rotation with electric limit system.
Two gpm (7.57lpm) open center hydraulic system.
Hydraulic oil reservoir with 7 gallon (26.5L) capacity built integral to pedestal.
Self locking worm gear rotation drive with shear ball bearing.
Boom articulation from 8 degrees below horizontal to 80 degrees above horizontal.
Electric rotation limit system.
Van mount pedestal and mounting hardware for low roof Transit van installation.
Hand held remote lower controls including 30 ft. cable and override.
Electric controls at platform including master control, emergency stop, and control cover.
Hydraulic power supplied by engine belt drive system.
Walk in hydraulic leveled 24 in. x 24 in. x 42 in. (.61m x .61m x 1.07m) end mounted fiberglass platform with door and vinyl cover
Non-lube bearings used at all pivot points.
Multi-link plastic hose carrier system through booms.
120V wiring to platform with GFCI receptacle.
12 volt DC backup pump.
Safety harness and lanyard.
Unit painted standard white urethane.
Two operators and service manuals.
ANSI A92.2 data plate.

Installation to include the following:

- Install VERSALIFT VANTEL-29-NE.
- Belt drive system and mounting hardware.

- Install and non-skid bumper extension.
- Install access step with center stop light on extension.
- Install SuperSprings on rear axle both sides.
- Install Masterack cab partition and shelving system and Prime Design roof ladder rack.
- Install two (2) turret mounted amber strobes.
- Install 1800 watt inverter with one Group 31 battery including battery box
- Install parking brake interlock, back up alarm and bucket rest
- Furnish rubber wheel chocks
- Fire extinguisher
- First aid kit
- 3 piece triangle warning kit
- Test ride completed unit for 1 Hour.
- Test and Certify per ANSI A92.

Notes:

No taxes have been included.

Chassis requirements available upon request.

Versalift Southeast,

Alex Euliss